

Mayor
John W. Minto
City Council
Ronn Hall
Laura Koval
Rob McNelis
Dustin Trotter

June 5, 2025

**TRAFFIC SIGNAL AND COMMUNICATIONS UPGRADES – ISSOLATED LOCATIONS
CIP 2023-09**

ADDENDUM NO. 1

To Prospective Bidders:

This Addendum No. 1 (2 pages in total) forms an essential part of the contract documents by revising the following:

1A CONTRACT DOCUMENTS

The following items are changes to the Contract Documents: No changes.

1B SPECIFICATIONS

The following items are changes to the Specifications:

1B-1 Section 87-1.03U Push Button Assemblies:

Delete the first paragraph and replace the following:

*The Contractor shall remove and install pedestrian push buttons with **Contractor** supplied Polara iN2 iNavagator 2-wire push button stations and iN2 system or approved equal in the traffic signal cabinets at locations identified on the plans.*

1C DRAWINGS/EXHIBITS

The following items are changes to the Drawings/Exhibits: No Changes.

1D RFI RESPONSES

The following items are responses to received RFI's for the project:

1D-1 Will the City of Santee take all responsibility for the testing of cabinets and equipment provided by the city to the contractor?

No testing will be required by the Contractor as all testing has been performed by the cabinet manufacturer.

1D-2 Will the City of Santee pay for and obtain all onsite tech support from each manufacturers rep for turn on support the day of controller swap over/install?

It is not expected that the manufacturer will be onsite during the turn on and the City itself will provide basic support including the configuration of the conflict monitor diode board and programming of the traffic signal controller.

1D-3 All city supplied cabinets and meter pedestals will come with anchor bolts and templates for mounting?

The Contractor shall furnish all required anchor bolts for the City supplied cabinets and service enclosure. The City supplied service enclosure will come with the base plate.

1D-4 Exhibit B Intersection Overview states the contractor will provide and install new audible pedestrian buttons, but, Section 87-1.03U (page 148) says they are city supplied. Which is correct?

The audible pedestrian push button systems shall be furnished and installed by the Contractor. See Section 1B-1 on page 1 for update to the specifications. Note that the additional material the updated iN2 cabinet card and the C1-Y cable required to convert the existing Polara audible push button systems to fit in a 332L cabinet will be provided by the City for the two locations with existing Polara iN2 systems.

Thank you,

A handwritten signature in blue ink, appearing to read "Jeff Morgan", with a stylized flourish at the end.

Jeff Morgan
Sr. Traffic Engineer