

Mayor  
John W. Minto  
City Council  
Ronn Hall  
Laura Koval  
Rob McNelis  
Dustin Trotter

April 27, 2023

To Prospective Bidders:

**CITYWIDE PAVEMENT REPAIR AND REHABILITATION PROGRAM 2023  
CIP 2023-05**

**ADDENDUM NO. 3**

This Addendum No. 3 (2 pages in total, including this cover page) forms an essential part of the contract documents by revising the following:

**3A CONTRACT DOCUMENTS**

The Engineer's Estimate is revised to \$1,314,000.00.

**3B SPECIFICATIONS**

Replace the Bid Schedule with the attached Bid Schedule, titled Addendum No. 3. This bid schedule shall be used when submitting a bid.

**303-5.1.4 Access**

Revise the following paragraph:

d) Pedestrian Ramps

Pedestrian ramps shall include the entire G-2 curb & gutter adjacent to the ramp from PCR to PCR (entire curve length). Pedestrian ramps shall be **per the Bid Schedule and Contract Exhibits**, unless otherwise noted or approved by the City. The first 15 feet of gutter transition to cross gutter at the PCR is part of the pedestrian ramp. Cross gutter replacement beyond these limits are to be included as cross gutter.

**3C DRAWINGS**

No changes.

**3D RFI RESPONSES**

No changes.

Receipt of this addendum shall be acknowledged by attaching and/or indicating as such on the Information Required of Bidder to the submitted Bid Documents.



Toby M. Espinola, P.E.  
Senior Civil Engineer

## BID SCHEDULE – Addendum No. 3

### CITYWIDE PAVEMENT REPAIR AND REHABILITATION PROGRAM 2023 CIP 2023-05

The estimated quantities and total cost herein set forth are for the purpose of comparison of bids only, and final payment will be made upon the basis of actual quantities and unit prices bid. The City reserves the right to vary these quantities by up to 25-percent without renegotiating the item unit prices.

BASE BID					
No.	Description	Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS	\$	\$
2	4" Asphalt Concrete Patching	20,040	SF	\$	\$
3	Skin Patching	23,097	SF	\$	\$
4	Cold Milling, Edge Grind (2", 4' Wide)	15,226	LF	\$	\$
5	Cold Milling, Header Cut (2", 20' Length)	9,860	SF	\$	\$
6	2" Asphalt Concrete Overlay	263,227	SF	\$	\$
7	Pavement Fabric	151,779	SF	\$	\$
8	Concrete Sidewalk (G-7)	445	SF	\$	\$
9	Concrete Curb & Gutter (G-2)	93	LF	\$	\$
10	Concrete Cross Gutter (G-12)	1,285	SF	\$	\$
11	Pedestrian Ramp, Type A (G-27)	11	EA	\$	\$
12	Pedestrian Ramp, Type C (G-29)	6	EA	\$	\$
13	Reset Property Marker	12	EA	\$	\$
14	Adjust Storm Drain Manhole To Grade	1	EA	\$	\$
15	Replace Street Monument Box, Frame and Lid	22	EA	\$	\$
16	Replace Sewer Cleanout Box, Frame and Lid	6	EA	\$	\$
17	Preparatory Roadway Surfacing Work	1	LS	\$	\$
18	Geotechnical Testing	1	LS	\$	\$
19	Water Pollution Control	1	LS	\$	\$
20	Striping Removal	1	LS	\$	\$
21	Striping	1	LS	\$	\$
21	Traffic Control	1	LS	\$	\$
Total Base Bid				\$	